



## EATON COUNTY DRAIN COMMISSIONER

### DILLON DRAIN

#### **NOTICE OF LETTING**

**DATE:** Tuesday, May 5, 2023  
**TIME:** 10:00 a.m.  
**LOCATION:** 1045 Independence Boulevard, Charlotte, Michigan 48813  
**QUESTIONS:** (989) 292-2191

The Eaton County Drain Commissioner will meet on the above date, time and location to receive construction bids for the Dillon Drain. Bids will then be opened and publicly announced. The Dillon Drain project will be let in one section as follows, each section having the length, average depth and width as set forth:

Estimated Quantity	Unit	Description
1,770	Lin. Ft.	Debris Removal
13,410	Lin. Ft.	Open Channel Cleanout (average 12' width, average 1' depth)
1	Lump Sum	Open Channel Clearing
<b>DRAIN CROSSINGS</b>		
30	Lin. Ft.	No. 3 - Sta. 34+92 – Private Crossing – Remove Existing Crossing and Replace with (2) 66" x 51" CMPA, 3" x 1" Corrugations, 12 Gauge, Bevel Ends 1.5 on 1
58	Lin. Ft.	No. 4 - Sta. 41+95 – Griffin Highway - Remove Existing Crossing and Replace with 142" x 91" CMPA 3" x 1" Corrugations, 12 Gauge, Bevel Ends 1.5 on 1
40	Lin. Ft.	No. 6 - Sta. 77+50 - Private Crossing - Remove Existing Crossing and Replace with 112" x 75" CMPA 3" x 1" Corrugations, 12 Gauge, Bevel Ends 1.5 on 1
1	Lump Sum	No. 8 - Sta. 93+42 – Battle Creek Rd - Cut Timber Piles and Remove Approx. 40 Cu. Yds. of Sediment
40	Lin. Ft.	No. 10- Sta. 107+75 - Private Crossing - Remove Existing Crossing and Replace with 112" x 75" CMPA 3" x 1" Corrugations, 12 Gauge, Bevel Ends 1.5 on 1
30	Lin. Ft.	No. 12- Sta. 135+98 - Private Crossing - Remove Existing Crossing and Replace with 103" x 71" CMPA 3" x 1" Corrugations, 12 Gauge, Bevel Ends 1.5 on 1
30	Lin. Ft.	No. 13- Sta. 146+67 - Private Crossing - Remove Existing Crossing and Replace with 95" x 67" CMPA 3" x 1" Corrugations, 12 Gauge, Bevel Ends 1.5 on 1
38	Lin. Ft.	No. 15- Sta. 160+22 - Private Crossing - Remove Existing Crossing and Replace with 81" x 59" CMPA 3" x 1" Corrugations, 12 Gauge, Bevel Ends 1.5 on 1
2	Each	12" – 18" H.D.P.E. Flared End Section (Install Only)
14,960	Lin. Ft.	12" – 36" H.D.P.E. Dual Wall Storm Sewer (Install Only)
160	Lin. Ft.	18" – 30" H.P. Storm Sewer (Install Only)
5	Each	24" – 36" H.D.P.E. Inlet Tee (Install Only)
26	Each	48" – 84" Dia. Manhole (Furnish and Install)

500	Sq. Yd.	Misc. Plain Riprap Protection (As Directed)
500	Lin. Ft.	Plain Riprap Toe of Slope Protection
500	Lin. Ft.	Plain Riprap Spillway
20	Each	12" – 24" Surface Outlet Tube
10	Each	4" – 10" Field Tile Outlet
25	Each	4" or 6" Field Tile Connections
3,200	Sq. Yd.	Mulch Blanket
1,000	Cu. Yd.	Subgrade Undercut and Backfill
115	Sq. Yd.	Gravel Road/Drive Restoration
6	Tons	Bituminous Drive Restoration (13A)
28	Each	Storm Drain Inlet Protection
1	Lump Sum	Misc. Seeding
1	Lump Sum	Traffic Control
1	Lump Sum	Cleanup and Restoration
	Various	Soil Erosion and Sedimentation Control

**Additional crossing work:**

Crossing No. 5 – STA 69+38 – Hydon Rd – Crossing work on the Hydon Rd crossing under separate contract will be completed in parallel with the above referenced work.

This Notice of Letting, the plans, specifications and bid proposal shall be considered a part of the Contract. The Contract will be let in accordance with the Contract Documents now on file at **Eaton County Drain Commissioner** and available to interested parties. Bids will be made and received in accordance with these documents. Bidding Documents, including plans and specifications, may be examined at the following locations:

***Spicer Group Inc. Website***

<https://www.spicergroup.com/> (Click on “Bidding” Tab)

Copies of Bidding Documents may only be obtained upon payment of \$22.00 through the Spicer Group bidding website via QuestCDN by entering Quest Project Number **8476960** on the website’s project search page. Please contact Quest CDN Customer Support at (952) 233-1632 or [info@questcdn.com](mailto:info@questcdn.com) for assistance in free membership registration, downloading, and working with the digital project information. An additional charge of \$50.00 will be required for sending out printed versions of the Bidding Documents.

**A MANDATORY pre-bid conference will be held on Tuesday, April 25, 2023, at 10:00 a.m. at the Eaton County Drain Commissioner’s Office, 1045 Independence Boulevard, Charlotte, Michigan 48813.** Representatives of the Eaton County Drain Commissioner and Engineer will be available at the pre-bid conference to discuss the Drain Contract. Prospective Bidders are required to attend and participate in the pre-bid conference. Attendance will be taken. Only bids from Bidders in attendance at the pre-bid conference will be opened. All other bids will be considered non-responsive and will be disqualified from bidding on the Drain Contract. The Engineer will transmit to all prospective Bidders of record such Addenda as the Engineer considers necessary in response to questions. Oral statements may not be relied upon and will not be binding or legally effective. **You must download the Contract Documents from QuestCDN to bid on the project, to be included on the plan holders list, and to receive Addenda.** The Contractor is responsible for ensuring all addenda have been received and acknowledged prior to submittal of the bid.

A 5% bid security deposit in the form of a cashier's check, money order, certified check or bidder's bond shall be submitted with any bids. No cash will be permitted. The security deposits of all unsuccessful bidders shall be returned after the Contract is awarded.

The Contract will be awarded to the lowest responsive and responsible bidder giving adequate security for the performance of the work and meeting all conditions represented in the Instructions to Bidders. The Contract completion date and the terms of payment will be announced at the time and place of letting. If no satisfactory bids are received, we reserve the right to reject any and all bids and to adjourn to a time and location as we shall announce.

The following is a description of the several tracts or parcels of lands constituting the Dillon Drain Drainage District:

That part of Carmel Township T.02N.-R.05W. as described:  
Sections 20, 27-33

That part of Walton Township T.01N.-R.05W. as described:  
Sections 4-9, 17-18